

# Installations manual for COMPACT3-9



Thank you very much for choosing our products.

Control box COMPACT3-9 consists of these parts:




3 pcs Cascade cable between the control boxes.



3 pcs control box



Connect the cables as the on picture.  Do not use.





Here are all the motor cables connected, if you only have 8 motors then the one of the inputs will be covered.



Do not use.



Input for handset.

#### **Installation (only for authorized personnel) Starting up:**

1. After connecting all the cables

After connecting all the cables, you must reset the system.

#### **Always reset the lifting system to zero before using for the first time:**

2. To make sure the lifting columns are down at the bottom – hold down-button for 10-30 seconds Release down-button. Hold the down-button in again for 10 seconds until a click (3x2 click) is heard.

**Note:** Before starting up, make sure that all drives/lifters are plugged in completely and correct and that there cannot be a collision while moving down.

3. **Operating:** Use the “Up” or “Down”-buttons to move the drives.

**Note:** Press “Down”-button until you hear all the clicks are stopped!

**Do not use the control box without all the motor cables and never reset the system with out double checking all the motor cables are correctly connected!!**

